BEKAERT

better together





65/60 **G**G

Length

Aspect ratio

DATASHEET

Characteristics

Material properties

Nom. tensile strength:	179.846795 (1240 l
Young's modulus:	29000 (200000 I
Strain at ultimate strength:	0.8

(60 mm)

MPa)) ksi MPa) 8 %

ksi

Geometry

Fiber family



Length (I) 2.3622 in.

Diameter (d)0.035433 in. (0.9 mm)

Aspect ratio (I/d) 65



Minimum EN 14889-1 dosage

25 lb/yd³ (15 kg/m³)

Fiber network

7522 ft/yd3 at 25 lb/yd3 (2999) m/m3 at 15 kg/m3) 1477 fibers/lb (3257 fibers/kg)

Dramix[®] family

3D Typical SFRC applications 4D Supreme serviceability control 5D Advanced structural applications



Product certificates*



* Product certificates are plant specific.

Product conformity

Dramix® conforms to ASTM A820, EN 14889-1 and ISO 13270 Class A.

System certificates



All Dramix® plants are ISO 9001 and ISO 14001 certified.

Packaging



BAGS 44 lb (20 kg) **BIG BAG** 2.420 lb (1.100 kg)

Handling



DRAMIX® 3D 65/60GG

Galvanized Glued

The original anchorage

Dramix[®] 3D is the cost-efficient fiber for standard statically indeterminate concrete structures that are submitted to regular static, fatigue and dynamic loadings.

Glue technology for three-dimensional reinforcement

Dramix[®] steel fibers are bundled with water-soluble glue. The glue helps avoiding fiber balling during mixing and ensures a homogeneous distribution of fibers throughout the concrete mix.

Bekaert Bekaert construction support

You can count on our support for each step of your project, from concept design to on-site quality support. Our services include recommendations on slab design, construction detailing, concrete optimization and automatic total quality control procedures. We are also happy to share our knowledge with you and your team

Feel free to ask us for a workshop or training on the topic of steel fiber reinforcement in your offices.



Bekaert reserves the right to modify, discontinue or rebrand this product at any time with or without notice. All information contained herein is general and may not be complete. For further details, please contact the local Bekaert office.